

TABELA ROBÓT ZIEMNYCH POD KANALIZACJĘ SANITARNA

Przebudowa układu drogowego w Wielkim Mędromierzu - droga powiatowa

Nr	Długość [m]	Rzędna	Rzędna	Głębokość	Wykop [m3]	Zasypanie [m3]
1	10.50	150.80	149.18	1.62	46.29	46.11
2	8.20	151.20	149.29	1.91	46.96	46.78
3	8.20	151.50	149.39	2.11	55.19	55.01
4	12.90	151.70	149.78	1.92	74.41	74.23
5	8.00	151.70	149.57	2.13	54.69	54.50
6	12.30	151.90	150.07	1.83	65.70	65.51
7	10.80	153.30	151.63	1.67	49.93	49.74
8	9.40	152.70	151.15	1.55	38.71	38.53
9	8.90	155.00	153.59	1.41	31.73	31.55
10	8.50	155.00	153.59	1.41	30.31	30.13
11	15.00	155.70	154.27	1.43	54.52	54.34
	112.70				548.43	546.43